

**SURVEY &
REMONUMENTATION**

FEB 21 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMENCING YEAR 2000
RECEIVED FOR RECORD
IRON COUNTY, MICHIGAN

00 DEC -5 PM 12: 50

L.C. Records: 1. 8, P. 222

Robert A. Goodreau
REGISTER OF DEEDS

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 43N R 36W	C-13
	T 44N R 36W	C-13
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert A. Goodreau in a field survey on May 10, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-1/C-13 Original corner established by Austin Burt, U.S. Deputy Surveyor, in 1847.

Original witnesses: Yellow Birch 20" N 77° E 52 links
Sugar Maple 12" N 80° W 24 links
Sugar Maple 14" S 24° W 29 links
Yellow Birch 15" S 59° E 39 links

Donald D. Lappala RLS restored corner position on 10 September 1964 using State Highway project plans and an existing reference monument. He also set a 2" x5' conc. Filled reference monument w/bronze tablet (Liber 3, Page 285).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-1/C-13 Found RR spike in monument box.

Found reference monument (2" concrete filled iron pipe w/ bronze tablet) set by Lappala described as: North 50.0 ft.

Found witness recorded by Lappala as: 9" Sugar Maple N 18° W 67.6' (102.4 links)

Corner record research on file with county representative.

PEER GROUP APPROVED
Don David Papp 11-14-2000
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1/C-13 Accepted corner as found.

Witnesses: 9" Spruce N 23° W 54.95' (NBT)
9" Maple spur N 13° W 67.85'
6" Maple S 25° E 123.30' (NBT)
7" Y. Birch S 31° W 114.52' (NBT)
Sign post North 1' of reference monument.

Note: Measurements taken to a nail in side of witnesses.

Signed by *R.A. Goodreau*
Surveyor's Michigan License No. 43053

Date July 1, 2000

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

