

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 44-45N R 31W

DESCRIPTION OF CORNER 1/4 corner between Section 4 and 33

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED December 6, 1968

WITNESSES TO CORNER..... W. Pine 24 S15 $\frac{1}{2}$ ^oW 212 lks. "1/4 S NBT"



W. Pine 17 S60 $\frac{1}{2}$ ^oW 184 $\frac{1}{2}$ lks. "1/4 S NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument replaced by proportionate measurement on line between a probable original section corner 40.035 chains east and township corner 199.52 chains west. Found no evidence of original post or its accessories or of any replacement monument or accessories. Distances east and west to swamp edges check fairly well. Corner is in an open marsh.

Bearing of section line is about S89^o49'W. Variation at this corner is 6^o00' West. Considerable local variation in the area.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

3/24/69

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68