

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 44-45N R 31W

DESCRIPTION OF CORNER 1/4 corner between Sections 6 and 31

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED November 21, 1968

WITNESSES TO CORNER..... Cedar 6 N67°E 18½ lks. "1/4 S NBT"



Bl. Spruce 8 S34°W 35 lks. "1/4 S NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established by proportionate measurement on line between township corner 39.386 chains west and a probable original section corner 200.167 chains east. Found a 14" dead cedar with old blazes S53°W 77 links from this point, and old line blazes going E and W from it, but no evidence of original corner or its accessories or of any replacement post or accessories. Corner is in a wet swamp.

Bearing of the section line is about S89°49'W.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

3/24/68

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68