

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 44-45N R 31W

DESCRIPTION OF CORNER East 1/16 corner between Sections 4 and 33

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED December 6, 1968

WITNESSES TO CORNER..... Bl. Spruce 6 S8°W 9 lks. "1/16 S BT"



Bl. Spruce 8 N15°E 31½ lks. "1/16 S BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner established by proportionate measurement on line between a probable original section corner 20.017 chains east and a township corner 219.536 chains west. Found no evidence that a corner had ever been established here or in the vicinity previously.

Corner is on high ground in a spruce-balsam thicket.

Bearing of section line is about S89°44'W. Variation at this corner is 10°30' West. Considerable local variation in the area.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED Arthur O. Enger DATE 3/24/69
REGISTERED LAND SURVEYOR

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68