

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 44-45N R 31W

DESCRIPTION OF CORNER West 1/16 corner between Sections 4 and 33

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED December 10, 1968

WITNESSES TO CORNER..... Wh. Spruce 9 S14°W 20½ lks. "1/16 S BT"



Bl. Spruce 6 N 7°W 23 lks. "1/16 S BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner established by proportionate measurement on line between a probable original section corner 60.052 chains east and a township corner 179.501 chains west. Found no evidence that a corner had ever been established here or in the vicinity previously. Found old E and W blazes on a burned white pine stub N49°W 52 links from corner.

Bearing of section line is about S89°49'W. Variation at this corner is 4°40'W. Considerable local variation in the area.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED Arthur O. Enger DATE 3/24/69
REGISTERED LAND SURVEYOR

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68