

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 44-45N R 31W

DESCRIPTION OF CORNER 1/4 corner between Sections 5 and 32

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED December 10, 1968

WITNESSES TO CORNER..... Wh. Spruce 15 N34°W 57½ lks. "1/4 S NBT"



Wh. Birch 8 N89½°W 12½ lks. "1/4 S NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed by proportionate measurement on line between a probable original section corner 120.100 chains east and the township corner 119.453 chains west. Found no visible evidence of the original post or its accessories or of any replacement monument or accessories, but did find blazes and foresters' paint marks for an approximate corner S35°W 60½ links from the corner, and also old line blazes going north from about the corner placed here.

Bearing of section line is about S89°49'W. Variation at this corner is 3°20' West. Considerable local variation in area, increasing in amount eastward until Fence River is reached.

SURVEYOR'S SEAL

SIGNED

Arthur O. Engler
REGISTERED LAND SURVEYOR

DATE

3/24/69

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68