

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 44-45N R 31W

DESCRIPTION OF CORNER West 1/16 corner between Sections 5 and 32

CORNER MONUMENT 1" I. D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED December 10, 1968

WITNESSES TO CORNER..... Bl. Ash 14 S89 $\frac{1}{2}$ ⁰E 21 lks. "1/16 S BT"



No others available.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner established by proportionate measurement on line between a probable original section corner 140.117 chains east and the township corner 99.436 chains west. No evidence that a corner had been established here or in vicinity previously. Corner is in a tag alder swamp.

Bearing of section line is about S89⁰49'W. Variation at this corner is 2⁰30' West. Considerable local variation in this area, increasing in amount eastward until Fence River is reached.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED Arthur D. Enger DATE 3/24/69
REGISTERED LAND SURVEYOR

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68