


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Iron COUNTY
T 44-45N R 31W

DESCRIPTION OF CORNER Section Corner 5, 6, 31, and 32
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap
DATE MONUMENT PLACED AND WITNESSED December 6, 1968
WITNESSES TO CORNER..... Cedar 6 S40 $\frac{1}{2}$ °W 8 lks. "S6 NBT"



Tamarack 5 S65 $\frac{1}{2}$ °E 25 lks. "S5 NBT"
Tamarack 8 N36°E 40 $\frac{1}{2}$ lks. "S32 NBT"
AND
Tamarack 7 N30°W 51 lks. "S31 NBT"

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established by proportionate measurement on line between a probable original section corner 160.133 chains east and the township corner 79.420 chains west. Found no identifiable evidence of original monument or its accessories. Found the point of a 4" cedar post of unknown age WNW'ly about two chains from corner established here, but no evidence of accessories and nothing to verify it as anything but an approximate corner. Spruce cruiser's tree nearby.

Bearing of the section line is about S89°49'W. Variation at this corner is 3°10' West. Considerable local variation in this area, increasing in amount eastward until Fence River is reached.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

3/24/69

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68