

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 44-45 R 31W

DESCRIPTION OF CORNER Section Corner 1, 2, 35, and 36

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED October 4, 1968

WITNESSES TO CORNER..... Bl. Spruce 4 N84°W 24½ lks. "S35 NBT"



Bl. Spruce 8 N 7°E 44½ lks. "S36 NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established by proportionate measurement between township corner 80,014 chains east and 1/4 corner 40,007 chains west. Found no evidence of original corner or its accessories or or any replacement monuments or accessories, but did find a 10" black spruce with blazes on four sides distant N4°W 71 lks. from corner set here.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur P. Enger
REGISTERED LAND SURVEYOR

DATE

3/19/69

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68