

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 44N R 31-32W

DESCRIPTION OF CORNER Section Corner 1, 6, 7, and 12

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED October 28, 1968

WITNESSES TO CORNER..... Cedar 13 N12°E 38½ lks. *S6 NBT*



Cedar 9 N 6°W 47½ lks. *S1 NBT*

W. Birch 11 S15°E 46 lks. *S7 NBT*

AND
W. Spruce 13 S51°W 36 lks. *S12 NBT*

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed at site of an L. E. S. post bearing date of September 12, 1931, set by Felix Mayer et al. Old L. E. S. maps indicate the presence of original corner evidence when the post was set, but the nature of the evidence is not specified. Found no identifiable original evidence at this time, but there are many old blazes on living and down trees in the vicinity, indicating long usage of the corner. Distance and direction to known corners to north check quite well.

SURVEYOR'S SEAL

SIGNED Arthur O. Enger DATE 3/19/69
REGISTERED LAND SURVEYOR

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing