

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY  
T 44-45N R 31W

DESCRIPTION OF CORNER Section Corner 4, 5, 32, and 33

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED November 27, 1968

WITNESSES TO CORNER..... Tamarack 5 N28°E 35½ lks. "S33 NBT"



Tamarack 4 N18°W 40 lks. "S32 NBT"

Tamarack 5 S77°W 53½ lks. "S 5 NBT"

AND

Tamarack 4 S19°E 62 lks. "S 4 NBT"

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established by proportionate measurement on line between a township corner 159.49 chains West and a probable original section corner 80.065 chains East. No identifiable evidence of original corner monument or its accessories or of any replacement monument or accessories. Found an approximate corner, a 3" tamarack with blazes on four sides, bearing S41°E 29 links from corner, with line blazes on trees to north. Distances to swamp edges north and west of corner show good agreement with original field notes.

SURVEYOR'S SEAL

SIGNED

*Arthur P. Enger*  
REGISTERED LAND SURVEYOR

DATE

2/19/69

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing