

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 44-45 R 31W

DESCRIPTION OF CORNER 1/4 corner between Sections 1 and 36

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED October 8, 1968

WITNESSES TO CORNER..... Red Pine 22 N20°E 102 lks. "1/4 S NBT"



Balsam Fir 7 S53°W 26 lks. "1/4 S NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed by proportionate measurement between Section Corners 40.007 chains to east and west. Found no evidence of original corner or its accessories or of any replacement monument or accessories, but did find a 4-inch aspen blazed on four sides for an approximate corner, N25°W 64 links from monument placed here.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED Arthur O. Enger DATE 3/19/69
REGISTERED LAND SURVEYOR

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68