

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY  
T 44-45N R 31W

DESCRIPTION OF CORNER 1/4 corner between Sections 3 & 34

CORNER MONUMENT Cross (+) chiseled on boulder

DATE MONUMENT PLACED AND WITNESSED October 9, 1968

WITNESSES TO CORNER..... Sugar Maple 9 S43°W 28½ lks. "1/4 S NBT"



Sugar Maple 7 N68°E 45 lks. "1/4 S NBT"

1" I.D. x 36" iron pipe with 4" aluminum cap placed 2.00  
links South of corner.  
AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established by proportionate measurement between Section Corners 40.23 chains to East and West. Found no visible evidence of the original corner monument or its accessories or of any replacement monument or accessories. Found evidence of an old line on old tree blazes east of corner.

Corner is on NW side of a steep hardwood ridge. The original field notes do not indicate the corner as being on a boulder, but the circumstances of proportionate measurements, in this case, caused the corner to fall as noted above.

Variation at this corner is about 7°00' East. There is considerable local variation in this area.

SURVEYOR'S SEAL

SIGNED

Arthur O. Enger  
REGISTERED LAND SURVEYOR

DATE

3/19/69

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68