

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Iron-Dickinson-Marquette COUNTY


T 44-45 R 30-31W

DESCRIPTION OF CORNER Section Corner 1, 6, 31, and 36 (also township corner)

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED September 27, 1968

WITNESSES TO CORNER..... White spruce 9 N45 $\frac{1}{2}$ °E 27 lks. "S31 NBT"



Jack Pine 13 N25°W 2 5 $\frac{1}{2}$ lks. "S36 NBT"

Jack Pine 13 S30°E 24 lks. "S6 NBT"

AND

White Pine 10 S86°W 75 lks. "S1 NBT"

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established by four-way proportionate measurement between section corner 78.58 chains east and 1/4 corners 40.60 chains south, 120.02 chains west and 119.86 chains north. Found no evidence of original monument or its accessories.

SURVEYOR'S SEAL

SIGNED Arthur O. Enger DATE 10/21/69
REGISTERED LAND SURVEYOR

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing