


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Iron COUNTY
T 44N R 31-32W

DESCRIPTION OF CORNER South 1/16 corner between Sections 1 and 6
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap
DATE MONUMENT PLACED AND WITNESSED May 2, 1969
WITNESSES TO CORNER..... White Spruce 4 S36°E 39½ lks. "1/16 S BT"



White Spruce 12 N50°W 65 lks. "1/16 S BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed midway on line between section corner 20.043 chains to South and 1/4 corner 20.043 chains to North.

Found a 1" squared picket bearing S78°E 14 lks., which has been used for an approximate corner.

Variation is 2°15' West at this corner.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

10/20/69

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68