

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 44N R 31-32W

DESCRIPTION OF CORNER 1/4 corner between Sections 1 and 6

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED May 2, 1969

WITNESSES TO CORNER..... Red Maple 5 N 1°E 47 lks. "1/4 S NBT"



White Spruce 6 S20°W 31 lks. "1/4 S NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed by proportionate measurement on line between a section corner 40.086 chains South and the township corner 38.543 chains North. Found no evidence of the original corner post or its accessories. Found a L. E. S. squared post S81°E 57 links from this point, dated June 24, 1931, but old L. E. S. maps do not indicate this post as being anything more than approximate.

Variation is 1°45' W at this corner.

SURVEYOR'S SEAL

SIGNED Arthur O. Enger DATE 10/20/69
REGISTERED LAND SURVEYOR

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68