

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 44N R 31W

DESCRIPTION OF CORNER 1/4 corner between Sections 4 and 9

CORNER MONUMENT 1" I.D. x 3/8" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED June 3, 1969

WITNESSES TO CORNER..... Cedar 11 N73°E 42 1/2 links "1/4S NBT"



Cedar 9 S3°E 45 links "1/4S NBT"

Bearings are magnetic.

AND _____

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed from two original BT's: Tam. 10 N33W 12 is a dead stub about 20 feet high with scribe marks plain on both upper and lower faces; Cedar 8 S14E 18 was dug up out of the moss and identified by scar growth around upper face. Tree otherwise badly rotted. Found the point of an old post S33E 13 links from the tamarack BT; also found an old squared up tree lying on the ground bearing S66E 10 1/2 links from corner and several blazes on nearby trees. Corner reported to me by George Divine, Area Forester.

SURVEYOR'S SEAL

SIGNED Arthur O. Enger DATE 2/26/70
REGISTERED LAND SURVEYOR

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68