

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Iron-Dickinson COUNTY


T 44N R 30-31W

DESCRIPTION OF CORNER 1/4 corner between Sections 7 and 12

CORNER MONUMENT 1" I. D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED August 20, 1969

WITNESSES TO CORNER..... W. Pine 13 S62°W 32 lks. "1/4S, NBT"



W. Pine 12 N71°W 35½ lks. "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established by proportionate measurement between an original section corner 39.945 ch. north and a re-established section corner 39.945 ch. south. Proceeding south from the section corner to the north, there is a \ominus 39' left deflection at the 1/4 corner, to give better conformity of the section line with the original field note calls.

Variation about $0^{\circ}10'$ West at this corner.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE February 22, 1972

Arthur O. Enger

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68