

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Iron-Dickinson COUNTY


T 44N R 30-31W

DESCRIPTION OF CORNER North 1/16 corner between Sections 13 and 18

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED September 9, 1969

WITNESSES TO CORNER..... W. Spruce 12 N44°E (mag.) 69½ lks. "1/16S, BT"



Balm of Gilead 10 N38½°W (mag.) 50 lks. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner established on line between section corner 19.973 chains north and 1/4 corner 19.973 chains south. No evidence that the corner had been established previously.

Variation 0°00'.

SURVEYOR'S SEAL

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

February 22, 1972

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68