

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Iron-Dickinson COUNTY


T 44N R 30-31 W

DESCRIPTION OF CORNER North 1/16 corner between Sections 7 and 12

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED August 20, 1969

WITNESSES TO CORNER..... Aspen 6 S4°W (mag.) 11½ lks. "1/16S, BT"



Balsam 7 S79½°W (mag.) 55½ lks. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner established on line between section corner 19.973 chains north and 1/4 corner 19.973 chains south. No evidence that the corner had been previously established. Variation at this corner is 0°20'W.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE February 22, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68