

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

Iron-Dickinson COUNTY


T 44N R 30-31W

DESCRIPTION OF CORNER South 1/16 corner between Sections 13 and 18

CORNER MONUMENT South 1/16 corner between Sections 13 and 18

DATE MONUMENT PLACED AND WITNESSED September 4, 1969

WITNESSES TO CORNER..... W. Pine 16 S40°W 24½ lks. "1/16S, BT"



W. Pine 19 S42°E 111½ lks. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner established on line between 1/4 corner 19.973 chains north and section corner 19.973 chains south. Corner is located on edge of swamp NW & SE; record indicates "enter swamp NW" at 20.00 chains north of section corner. 4.82 chains north to "stream 12 lks. wide course east"; record indicates such a stream 4.98 chains north of corner. No evidence that the corner had been previously established. Variation at this corner 0°00'.

SURVEYOR'S SEAL

SIGNED

*Arthur O. Enger*  
REGISTERED LAND SURVEYOR  
Arthur O. Enger

DATE February 22, 1972

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68