

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Iron-Dickinson COUNTY


T 44N R 30-31W

DESCRIPTION OF CORNER Section Corner 19, 24, 25, and 30

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED September 4, 1969

WITNESSES TO CORNER..... Yellow Birch 16 N87°W (mag.) 37 lks. "S24, NBT"



Sugar Maple 12 N 1°E (mag.) 35 lks. "S19, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a concrete monument with brass cap, by Wisconsin-Michigan Power Co., N43°E 33.2 links; probably placed in 1943 by Holland, Ackerman, & Holland, Consulting Engineers, of Chicago, Illinois and Ann Arbor, Michigan. Monument set at site of a found wood post.

Found nothing in the record or on the ground to support the WMPC monument. As total measured distance between an original section corner 1 mile S and another 3 miles N is 319.56 ch., compared to 320.00 ch. record distance; and since proportionate measurements to natural objects called for along the line agree well with the record measurements, it was felt by the undersigned that proportionate measurements were better evidence of the true corner location than was the wood post found by WMPC. Hence, corner was re-established proportionately on line.

Variation 0°20'West.

SURVEYOR'S SEAL

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE February 28, 1972

DISTRIBUTION:

Arthur O. Enger

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68