

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

Iron-Dickinson COUNTY


T 44N R 30-31W

DESCRIPTION OF CORNER Section Corner 13, 18, 19, and 24

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap,

DATE MONUMENT PLACED AND WITNESSED September 4, 1969

WITNESSES TO CORNER..... Red Maple 6 S40 $\frac{1}{2}$ <sup>o</sup>E (mag.) 40 lks. "S19, NBT"



Red Maple 6 N77 $\frac{1}{2}$ <sup>o</sup>E (mag.) 72 lks. "S18, NBT"

Distances are horizontal.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established on line between an original section corner 159.78 ch. S and a re-established section corner 79.89 ch. N. Corner is on a west facing slope of a high, narrow N & S ridge, just below the crest. Variation is 0 20' East.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

*Arthur O. Enger*  
REGISTERED LAND SURVEYOR  
Arthur O. Enger

DATE February 28, 1972

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68