

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Iron-Dickinson COUNTY


T 44N R 30-31W

DESCRIPTION OF CORNER South 1/16 corner between Sections 19 and 24

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED September 9, 1969

WITNESSES TO CORNER..... Basswood 13 N60°E (mag.) 50 lks. "1/16S, BT"



Sugar Maple 13 S72°W (mag.) 33½ lks. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner established on line between re-established section corner 19.972 ch. S and re-established 1/4 corner 19.972 ch. N. Top of 12 ft. high ridge is about 1 ch. N of corner, as mentioned in original field notes. Found old N & S line blazes on trees N of corner and a 15" elm with old blazes on 4 sides due E 35 lks., for an approximate corner. No evidence that the corner had been established previously. Variation 0°00'.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE March 3, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68