

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Iron-Dickinson COUNTY


T 44N R 30-31W

DESCRIPTION OF CORNER North 1/16 corner between Sections 19 and 24

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED September 8, 1969

WITNESSES TO CORNER..... Sugar Maple 7 N17 $\frac{1}{2}$ °E (mag.) 19 $\frac{1}{2}$ lks. "1/16S, BT"



Sugar Maple 4 S57°W (mag.) 6 lks. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner established on line between re-established section corner 19.972 ch. N and re-established 1/4 corner 19.972 ch. S. Found E & W line blazes on a 4" maple S57°W 6 lks from corner. No evidence that the corner had been established previously.

Variation 0°00'.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

March 3, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

Arthur O. Enger