STATE OF MICHIGAN DEPARTMENT OF NATURAL RESOURCES



\bigcup	

						Iron		COUNTY	
					T	44N	R _	31W	
ESCRIPTION OF CORNERS	ection Corn	er 4,	, 5, 8	, and 9)			<u>.</u>	
ORNER MONUMENT1" I.D	. x 36" iro	n pip	e wit	h 4" al	umin	um cap.			
ATE:MONUMENT PLACED AND WI	TNESSED	Nove	ember	25, 197	70				
TNESSES TO CORNER	Cedar	12 N	120°E	(mag.)	24.0	ft. "S4,	NBT"		
N	Red Maple	5 8	34 ⁰ W	(mag.)	17.2	ft. "S8,	NBT"		
	Y. Birch	15 S	578°E	(mag.)	48.0	ft. "S9,	NBT"		
A	ND								
CIRCLE CORNER REGISTERED									

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a 3/4" I.D. iron pipe and point of an old wood post in place as set by unknown party, with an old cruiser's register tree bearing dates from the 1920's 858°W 21.8 ft. from it. Corner accepted as found. It lies 79.00 ch. S of a re-established corner on the twp. line (record 78.90 ch.) and 40.48 ch. W of an original 1/4 corner bet. Sec. 4 & 9 (record 40.19 ch.).

SURVEYOR'S SEAL

SIGNED

DECIGREDED LAND CO

DATE March 17, 1972

DISTRIBUTION:

Arthur O, Enger

County Courthouse Area Forester (Regions I & II) District or Region Surveyor Forestry Div., Lansing

R 4047 Rev. 10/68