

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 44N R 31W

DESCRIPTION OF CORNER South 1/16 corner between Sections 4 and 5

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED November 25, 1970

WITNESSES TO CORNER..... Cedar 7 S60 $\frac{1}{2}$ ^oE (mag.) 34.4 ft. "1/16S, BT"



Cedar 8 N51 $\frac{1}{2}$ ^oE (mag.) 34.2 ft. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner established on line between section corner 20.025 ch. S and 1/4 corner 20.025 ch. N. No evidence that the corner had been established previously.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE March 17, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68