

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 44N R 31W

DESCRIPTION OF CORNER North 1/16 corner between Sections 4 and 5

CORNER MONUMENT 3" x 3" x 6½' squared cedar post scribed "1/16, 4, 5"

DATE MONUMENT PLACED AND WITNESSED November 25, 1970

WITNESSES TO CORNER..... Sugar Maple 4 N39½°E (mag.) 6.0 ft. "1/16S, BT"



Sugar Maple 3 N21°W (mag.) 5.3 ft. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner established by proportionate measurement on line between 1/4 cor.
20.025 ch. S and section corner 18.925 ch. N.

No evidence that the corner had been established previously.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Eger
REGISTERED LAND SURVEYOR
Arthur O. Eger

DATE

March 17, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68