

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 44N R 31W

DESCRIPTION OF CORNER 1/4 corner between Sections 4 and 5

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED November 25, 1970

WITNESSES TO CORNER..... Sugar Maple 8 S61°E (mag.) 28.3 ft. "1/4S, NBT"



Sugar Maple 8 N47°E (mag.) 19.5 ft. "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a length of 3/4" electrical conduit S44°W (mag.) 34.9 ft. from corner, for an approximate corner. Nothing to support it as being at site of the original corner. Celotex Corp. location poster nearby.

Corner re-established by proportionate measurement on line between section corner 40.05 ch. S and section corner 38.95 ch. N.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

March 17, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68