

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Iron

_____ (County)	Located in:	Corner Code #
1. Public Land Survey	T 44N R 31W	A4
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 19 T _____ R _____	2
	S 18 T _____ R _____	3
3. Miscellaneous Property in Sec.	S 7 T _____ R _____	10
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Keith Sackett, in a field survey on January 5, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

A4	2	3	10
Original monument and accessories not found.	Not set on original survey. Found pipe N00-12-47E 35.62'	Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A4	2	3	10
Restored midway and on line.	Established midway and on line.	Established midway and on line.	Established midway and on line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1" 10 x 32" IP w/4" aluminum cap.	Set 1" 10 x 32" IP w/4" aluminum cap.	Set 1" 10 x 32" IP w/4" aluminum cap.	Set 1" 10 x 32" IP w/4" aluminum cap.
7" white birch N48E 6.6' 1/4s NBT	28" white pine N44E 20.3' 1/16s BT	4" maple N67E 4.1' 1/16s BT	4" balsam S06E 12.0' 1/16s BT
5" sugar S51W 7.4' 1/4s NBT	16" white pine S62E 42.9' 1/16s BT	6" maple N01E 1.7' 1/16s BT	8" balsam N24E 12.3' 1/16s BT
2" sugar S21E 16.4' 1/4s NBT	4" aspen B82W 6.2' 1/16s BT	3" spruce S29W 7.7' 1/16s BT	8" white birch N70W 18.3' 1/16s BT
4" sugar N29W 13.4' 1/4s NBT			7" balsam S40W 43.0' 1/16s BT
			7" white birch squared north 6.3'

Signed by Keith Sackett Date 1-19-89

Surveyor's Michigan License No. 19006