

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron	Located In:	Corner Code <i>##</i>
<small>(County)</small>		
1. Public Land Survey	T <u>44N</u> R <u>31W</u>	<u>89</u>
	T <u> </u> R <u> </u>	<u>C7</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u>18</u> T <u> </u> R <u> </u>	<u>7</u>
	S <u> </u> T <u> </u> R <u> </u>	<u>18</u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3	1	2	3	4	5	6	7	8	9	10	11	12	13
4	1	2	3	4	5	6	7	8	9	10	11	12	13
5	1	2	3	4	5	6	7	8	9	10	11	12	13
6	1	2	3	4	5	6	7	8	9	10	11	12	13
7	1	2	3	4	5	6	7	8	9	10	11	12	13
8	1	2	3	4	5	6	7	8	9	10	11	12	13
9	1	2	3	4	5	6	7	8	9	10	11	12	13
10	1	2	3	4	5	6	7	8	9	10	11	12	13
11	1	2	3	4	5	6	7	8	9	10	11	12	13
12	1	2	3	4	5	6	7	8	9	10	11	12	13
13	1	2	3	4	5	6	7	8	9	10	11	12	13

I, Keith Sackett, in a field survey on January 8, 1989, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

<u>89</u>	<u>C7</u>	<u>7</u>	<u>10</u>
Original monument and accessories not found. Found WI-NI Power Co. monument.	Original monument and accessories not found. Found old post that fits land calls east and west and section corner south. Has been used as corner for many years.	Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

<u>89</u>	<u>C7</u>	<u>7</u>	<u>10</u>
Restored at WI-NI Power Co. monument.	Restored at old post.	Established midway and on line.	Established midway and on line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>89</u>	<u>C7</u>	<u>7</u>	<u>10</u>
WI-NI Power Co. concrete monument w/brass cap.	Set 1" 10 x 30" IP w/4" aluminum cap.	Set 1" 10 x 32" IP w/4" aluminum cap.	Set 1" 10 x 32" IP w/4" aluminum cap.
12" white pine B45E 95.2' 830	12" red pine W43E 14.0' 817	30" white pine W02E 34.0'	10" red pine S88W 142.6' 1/16s
NBT	NBT	1/16s BT	BT
30" white pine W54E 90.0' 819	10" red pine W74W 4.5' 818 NBT	12" maple B24E 16.8' 1/16s BT	12" red pine W70E 71.0' 1/16s
NBT	5" maple B51E 9.0' 820 NBT	4" cherry B53W 21.4' 1/16s BT	BT
12" white pine W08W 101.4' 829			8" white pine W09W 137.4'
NBT			1/16s BT

Signed by Keith Sackett Date 1-19-89

Surveyor's Michigan License No. 19008