

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
 town _____
 County _____

	Located in:	Corner Code #
1. Public Land Survey	T 44N R 31W	C8
	T _____ R _____	C9
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S 19 T _____ R _____	14
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Register of Deeds Stamp & File Number _____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Keith Sackett, in a field survey on January 3, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

A. Description of original monument and accessories and/or subsequent restoration:

C8	C9	14
Original monument and accessories not found.	Original monument and accessories not found. Found NI-NI Power Co. monument.	Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C8	C9	14
Restored midway and on line.	Restored at NI-NI monument.	Established midway and on line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C8	C9	14
Set 1" 10 x 32" IP w/4" aluminum cap.	NI-NI Power Co. concrete monument w/brass cap.	Set 1" 10 x 32" IP w/4" aluminum cap.
6" white pine N35W 34.7' 1/4s NBT	24" white pine S59E 14.9' S29 NBT	10" maple S87E 9.8' 1/16s BT
12" white pine N76W 32.6' 1/4s NBT	10" red pine S13W 56.5' E30 NBT	8" white pine S35E 29.4' 1/16s BT
8" balsam S43E 14.1' 1/4s NBT	8" white birch N30W 31.6' S19 NBT	14" red pine N70W 31.1' 1/16s BT

Signed by Keith Sackett Date 1-19-89

Surveyor's Michigan License No. 19004