

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
 T_{44N}
 R_{15W}

County	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>15W</u>	<u>A7</u>
	T _____ R _____	<u>AB</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>19</u> T _____ R _____	<u>1</u>
	S _____ T _____ R _____	<u>3</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

I, Keith Sackell, in a field survey on August 14, 19 88, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A7	AB	1	3
Original monument and accessories not found. Found NI-NI cone monument w/brass cap.	Original monument and accessories not found.	Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A7	AB	1	3
Restored at NI-NI monument.	Restored midway on line.	Established by proportion on line.	Established midway on line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A7	AB	1	3
NI-NI cone monument w/brass cap.	Set 1" 10 x 32" IP w/aluminum cap.	Set 1" 10 x 32" IP w/4" aluminum cap.	Set 1" 10 x 32" IP w/4" aluminum cap.
12" cedar N40E 27.0' B10, NBT	5" sugar N72E 9.9' 1/4s NBT	5" spruce S51W 3.9' 1/16s BT	6" spruce N33W 17.0' 1/16s BT
12" cedar S10E 3.6' B19, NBT	4" sugar S23E 12.0' 1/4s NBT	9" tamarack S20E 21.6' 1/16s BT	5" spruce S27W 12.4' 1/16s BT
10" cedar S82W 12.7' B24, NBT	5" sugar S26W 17.5' 1/4s NBT	BT	3" spruce S36E 10.9' 1/16s BT
		4" spruce N30E 24.2' 1/16s BT	

Signed by Keith Sackell Date January 18, 1989

Surveyor's Michigan License No. 19006