

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Iron

	Located In:	Corner Code #
1. Public Land Survey	T 44N R 31W	87
	T _____ R _____	E6
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S 17 T _____ R _____	3
	S _____ T _____ R _____	14
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Keith Backett, in a field survey on February 7, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

87	E6	3	14
Original monument and accessories not found. Found old cedar post that fits reasonably close to midway on line between corners east and west. Post has been used as corner for many years.	Original monument and accessories not found.	Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

87	E6	3	14
Restored at old post.	Restored midway and on line.	Established midway on line.	Established midway on line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

87	E6	3	14
Set 1" I.B. by 36" I.P. w/4" aluminum cap.	Set 1" I.B. by 36" I.P. w/4" aluminum cap.	Set 1" I.B. by 7" I.P. with plastic cap.	Set 1" I.B. by 32" I.P. w/4" aluminum cap.
5" maple N07E 15.7' 1/48 NBT	12" sugar N64W 12.2' 1/48 NBT	dead 12" cedar N24E 48.6' 1/168 BT	8" sugar N31E 13.4' 1/168 BT
9" maple N03E 13.9' 1/48 NBT	28" white pine N10E 30.9' 1/48 NBT	dead 12" cedar N54E 7.2' 1/168 BT	9" sugar S74S 20.4' 1/168 BT
4" maple S63W 12.6' 1/48 NBT	12" cedar N06E 34.4' 1/48 NBT	set squared cedar post.	10" sugar N11W 13.4' 1/168 BT
			squared 10" aspen north 2.0'

Signed by Keith Backett Date 2/17/89
 Surveyor's Michigan License No. 19004

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 22, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

