

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Area	Located in:	Corner Code #
(County)		
1. Public Land Survey	T 44N R 31W	K7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Jun 16 1997

I, Stephan J. Szyszkeski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
(K7) Corner common to Sections 13-14-23-24. Corner established in 1849 by John Burt, D.S.: "Set Cedar post corner of Sections 13,14,12 & 24. Y. Birch 18 S40E 37, N. Pine 24 N75W 23". Examination of the dates in the original record indicate that the initial line run in this township was the E-W midline.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K7) Original post not recovered. Monumented the corner at record bearing and distance from the remains of the W. Pine bearing tree, found as a rotting stump of correct size, with no markings. The Y. Birch BT now falls in a marshy backwater of the artificially created Michigan Reservoir. I recovered a long-ago rotted stump of a tree at record bearing and distance for the Y. Birch, but the stump did not appear to be that of a Y. Birch. Recovered monumented corners 5291.7' East (S280 R) and 2659.9' West (2640 R). This position checks with the original "west end of ridge" call 5 chains south, and with top of hill and ridge calls east and west, when these calls are interpreted as being on the random E-W midline. At the position for the corner, I placed a 1" I.D. x32" iron pipe capped with a 4" dia. cast aluminum MONR tablet, appropriately stamped. The corner falls on the N. edge of an open willow marsh and at the south edge of a spruce/poplar stand.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K7) Set 1" pipe with 4" MONR cap.
Blazed and scribed the following bearing trees:
4" Spruce N72W 14.0' "S14 NOT"
6" Spruce N19E 36.8' "S14 NOT"
8" Spruce N85E 24.1' "S13 NOT"
8" Spruce S53E 52.4' "S24 NOT"
Placed a 3" squared spruce post adjacent. Bearings are magnetic.



Signed by Stephan J. Szyszkeski
Surveyor's Michigan License No. 33986

Date Sept 8, 1997

For the Michigan Department of Natural Resources - Forest Management Division