

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Iron</u>	Located in:	Corner Code #
(Contd)		
1. Public Land Survey	T 44R 31W	E4
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jun 16 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
 (E4) Quarter corner common to Sections 11-12. Corner established in 1849 by John Burt, D.S. "North between Secs. 11 & 12... 40.00 Set Y. Birch Cr. Section Post. N. Pine 30 S81W 14, do 24 S27E 24. Descend from post, 44.00 Foot of hill and enter sup. E&M; 50.00 leave swamp SE". Mr. Ron Willard, a long-time local land owner told me that Norman T. Thompson, RLS monumented this corner and the 1/16 to the north in the 1950's during a weekend survey done for Mr. Willard's father.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E4) Original post not recovered. Monumented the corner at record bearing and distance from the stump remains of the two N. Pine bearing trees, both found of proper size, but in poor condition with no markings visible. Monumented original corners were found 2637.7' North (2640 R) and 2610.8' South (2640 R). This corner was recovered about 12' east of a straight line between them. From the corner monumented, the call to "foot of hill and enter swamp" and "leave swamp" check. The swamp edges, particularly the acute bearing of the swamp edge at "leave" corroborated position of this corner. I recovered a 1/2" iron pipe with a fitting S76E 49.7' from the corner. Mr. Willard says that he believes this pipe to represent Mr. Thompson's position but that it may not be the same monument Mr. Thompson set. The pipe in no way fits the record and I do not believe it perpetuates the original position. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDMR tablet appropriately stamped.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E4) Set a 1" pipe with 4" MDMR cap.
 Blazed and scribed the following new bearing trees:

8" Sugar N66W 19.1'	"1/4S HBT"
10" N. Pine N17E 57.8'	"1/4S HBT"
16" N. Pine N63E 62.5'	"1/4S HBT"
15" N. Pine S61E 36.1'	"1/4S HBT"
8" Sugar S14W 47.8'	"1/4S HBT"

Bearings are magnetic.



Signed by

Stephan J. Szyszkoski

Date

Sept. 8, 1997

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division