

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Area Located in: Corner Code #
 (County)

1. Public Land Survey T___ R___
 T___ R___
 T___ R___
 T___ R___

2. Property Controlling in Section S__12 T__44R__31W__
 S__12 T__44R__31W__

3. Miscellaneous Property in Sec. S___ T___ R___
 S___ T___ R___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

10 Jun 23 1997
 3 Jun 18 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
 (3-Sec. 12) North 1/16 corner common to Sections 11-12. Corner not established in the original survey. Mr. Ron Willard, a long-time local resident told me that Mr. Norman T. Thompson, ALS, established this corner in the 1950's during a weekend survey for Mr. Willard's father. Mr. Willard also said that the monument which Mr. Thompson placed had subsequently been moved.
 (10-Sec.12) South 1/16 corner between Sections 11-12. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (3-Sec. 12) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a straight line between Section corner 1318.86' North and Quarter corner 1318.86' South. At the position for the corner I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. From the corner monumented, a metal fence post representing the altered Thompson position was found N38E 91 feet. Corner placed and witnessed by B. Wheeler and D. Laupela, Baraga District Office, MDNR. Corner is located approx. 75 feet (paced) East of a gate on a N-S trail road, and approx. 40 feet (paced) north of and e-w trail.
 (10-Sec. 12) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a straight line between Quarter corner 1305.4' North and Section corner 1305.4' South. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by D. Laupela and B. Wheeler, Baraga District Office, MDNR.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (3) Set 1" pipe with 4" MDNR cap. Blazed and scribed the following:
 16" W. Pine N22E 36.5" "N1/16 0T"
 22" W. Pine N23W 71.7" "N1/16 0T"
 15" W. Pine S46W 17.1" "N1/16 0T"
 5" Spruce S49E 12.3" "N1/16 0T"
 Placed a 4" squared spruce post adjacent. Bearings are magnetic.

(10) Set 1" pipe with 4" MDNR cap. Blazed and scribed the following:
 10" W. Spruce N78E 19.7" "1/16S 0T"
 18" W. Pine S77E 39.8" "1/16S 0T"
 6" W. Spruce S84W 16.8" "1/16S 0T"
 8" Double Maple N42W 37.4" "1/16S 0T"
 Placed a squared cedar post adjacent. Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date Sept. 8, 1997
 Surveyor's Michigan License No. 33986