

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron	Located in:	Corner Code #
(Contd)		
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>26</u> T <u>44N</u> R <u>31W</u>	<u>2</u>
	S <u>12</u> T <u>44N</u> R <u>31W</u>	<u>16</u>
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

16 Jun 24 1997
 2 Jul 22 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	13	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (2-Sec. 26) East 1/16 corner between Section 23-26. Corner not established in the original survey. Found no subsequent record.
 (16-Sec. 12) East 1/16 corner between Sections 12-13. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(2-Sec. 26) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a line of mean true bearing between Quarter corner 1323.9' West and Section corner 1323.9' East. The Section corner falls in the Michigan Reservoir. 1/16 position was determined by the WMPCO witness corner on the west shore. The Witness corner is 923.90' easterly of this 1/16 corner. At the position for the 1/16 corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by D.Laapala and B. Wheeler, Baraga District Office, MDNR.
 (16-Sec.12) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a line of mean true bearing between Section corner 1327.33' East and Quarter corner 1327.33' West. At the position for the corner I placed a 1" I.D. x32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by B.Wheeler and D.Laapala, Baraga District Office, MDNR. The corner lies 211' N60E (mag.) from a lone 23" W. Pine located on the north side of a trail road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(2) Set 1" pipe with 4" MDNR cap.
 Blazed and scribed the following:
 6" Sugar N69E 14.7' "1/16S BT"
 10" Sugar S43E 29.0' "1/16S BT"
 6" Sugar S11E 27.9' "1/16S BT"
 4" Maple S15W 30.0' "1/16S BT"
 A squared 9" Maple bears N70W 1.3' distant. Bearings are magnetic.

(16) Set 1" pipe with 4" MDNR cap.
 Blazed and scribed the following:
 5" Cherry N85E 2.7' "1/16S BT"
 30" White Pine N51W 64.7' "1/16S BT"
 10" Spruce S88W 45.5' "1/16S BT"
 5" Cherry S33E 22.0' "1/16S BT"
 Placed a squared cherry post adjacent.
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date Sept. 8, 1997
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division