

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron	Located in:	Corner Code #
(County)		
1. Public Land Survey	T <u>44N</u> R <u>31W</u>	<u>18</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jun 30 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (18) Quarter corner common to Sections 23-24. Corner established in 1849 by John Burt: "Set Neal Cr. Section Post. Sugar 12 S20E 65, N. Pine 30 N25W 30". Corner shown on map prepared for Wisconsin-Michigan Power Company by Holland, Ackerman and Holland, Consulting Engineers, Revised 12-7-53, numbered 6-154-66. Corner is described as "square concrete monument with brass cap. 4" poplar N18W 30.2', 4" poplar S83W 15.0', 4" poplar S74E 28.2'".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(18) Original post and accessories not recovered. The WMPCO monument and their accessories were not recovered despite an extensive search spanning four separate attempts. The corner location falls in the backwater of the Michigamme Reservoir. I consider the WMPCO to be lost and reestablish the corner midway and on a line of mean true bearing between Section corners 2634.61' North and South. The Southerly Section Corner also falls in the backwater of the reservoir. It's position was determined by a WMPCO witness monument on the west shore. The Quarter corner, being inaccessible, was monumented with a WITNESS CORNER 100.00' North of the corner position and on a line between the Quarter corner and the Section corner common to Sections 13-14-23-24. At the position for the WITNESS CORNER, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, stamped to read: "T44N R31W WIT COR 1/4 23/24 CORNER IS 100 FT. 50." Corner placed and witnessed by D.Wheeler and D.Lampala, Baraga District Office, MDNR. The witness corner is approximately 70' north of the current water's edge.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (18) Set a 1" pipe with 4" MDNR cap
 witness corner 100.00' North of the corner position on the Section line.
 Blazed and scribed the following:
 9" R. Pine N20W 47.5'
 7" Maple S60W 50.1' (slope dist.)
 16" R. Pine S32W 39.6' (slope dist.)
 16" Spruce S80E 138.4'
 Placed squared spruce post adjacent.
 Bearings are magnetic. Dist. are horizontal unless noted.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan Licensed No. 33986

Date Sept. 8, 1997

For the Michigan Department of Natural Resources - Forest Management Division