

59.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron <small>(County)</small>	Located in:	Corner Code #
1. Public Land Survey	T 44N R 31W	J9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S 24 T 44N R 31W	3
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

3 Jul 01 1997
J9 Jul 08 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
(J9) Quarter corner common to Sections 23-26. Corner established in 1849 by John Burt: "Set qr. Sec. post, Y. Birch 4 N32E 23, Fir 12 S54W 11". Corner shown on a map prepared for Wisconsin Michigan Power Company titled "Michigan River-Way Storage Dam Land Ties and Benchmarks" by Holland, Ackerman, and Holland Rev. 12/7/53, map# G-154-66. Corner is described as "Set concrete monument with brass cap. 6" Pop N58E 68.0', 12" P.Stump S35E 43.4', 2" Pop. N52W 18.7". Found no subsequent record.
(3-Sec. 24) North 1/16 corner between Sections 23-24. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J9) Original post and accessories not recovered. Recovered the WMPCO monument, a 7" truncated right rectangular concrete pyramid with a 3" sq. brass tablet affixed on top stamped "Wisconsin Michigan Power Company 44-31 1/4 23,26". The WMPCO witnesses were not recovered. The position of the monument is reasonable compared to section corner monuments east and west. I accepted the monument as the best available evidence of the position of the original corner. Left the monument in place and marked four new witnesses as described below. Corner witnessed by B.Wheeler and D.Lampela, Baraga District Office, MDNR.
(3-Sec. 24) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a line of mean true bearing between Section corner 1317.3' north and Quarter corner 1317.3' South. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office, MDNR. The corner is located in an aspen cutting about 50' N. of E. edge.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J9) Found WMPCO concrete monument.	(3) Set 1" pipe with 4" MDNR cap.
Blazed and scribed the following:	Blazed and scribed the following:
18" Twin W. Pine S44N 30.2' 1/4S NBT	16" Maple S75E 87.2' 1/16S BT
14" W. Pine S14N 51.1' 1/4S NBT	5" Ironwood N60E 105.3' 1/16S BT
10" Spruce N11E 58.0' 1/4S NBT	6" Maple S83W 37.1' 1/16S BT
16" W. Pine N30W 73.4' 1/4S NBT	Placed a squared post adjacent.
a 3' tall 1" ID iron pipe is adjacent.	Bearings are magnetic.
Bearings are magnetic.	



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date Sept. 8, 1997

For the Michigan Department of Natural Resources - Forest Management Division