

62.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| Iron <u> </u> (County) | Located In: | Corner Code # |
|---|------------------|---------------|
| 1. Public Land Survey | T 44N R 31W | L6 |
| | T R | _____ |
| | T R | _____ |
| | T R | _____ |
| 2. Property Controlling In Section | S 24 T 44N R 31W | 8 |
| | S T R | _____ |
| 3. Miscellaneous Property in Sec. | S T R | _____ |
| | S T R | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

8 Jul 31 1997
L6 Jul 29 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:
(L6) Center of Section 13. Corner not established in the original survey. Found no subsequent record.
(8-Sec. 24) West 1/16 corner, Section 24. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

(L6) Found no evidence of prior monumentation at the corner position. Established the corner at the intersection of straight lines connecting opposite quarter corners. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. From the corner monumented, I found a 1 1/4" iron pipe, placed by unknown parties, S40E 47.2' at the intersection of blue paint lines to the north and east. Corner placed and witnessed by B.Wheeler and D.Lampela, Baraga District Office, MDNR.

(8-Sec. 24) found no evidence of prior monumentation at the corner position. Established the corner midway and on a straight line between Quarter corner 1320.09' west and Center of Section 1320.09' East. The Center of Section position was determined at the intersection of straight lines connecting opposite 1/4 corners but was not monumented during this survey. At the position for the West 1/16 corner, I placed a 1" I.D. x 32" iron pipe capped with a yellow plastic capped stamped "MICK D.M.R. P.S. 33986". Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office, MDNR.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(L6) Set 1" pipe with 4" MDNR cap. Blazed and scribed the following:
14" W. Spruce N29E 61.6' "C1/4 BT"
16" W. Spruce S64.5E 60.8' "C1/4 BT"
14" W. Pine S10E 50.8' "C1/4 BT"
7" W. Spruce S22W 23.6' "C1/4 BT"
Placed squared maple post adjacent. Bearings are magnetic.

(8) Set 1" pipe with cap #33986. Blazed and scribed the following:
3" Aspen N64E 13.4' "1/16S BT"
3" Aspen S73E 12.0' "1/16S BT"
5" Maple S53W 52.5' "1/16S BT"
2" Maple S88W 40.2' "1/16S BT"
Corner falls in a large aspen regeneration (2"-3" trees). Bearings are magnetic. Placed a squared aspen post adjacent.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date Sept. 8, 1997

For the Michigan Department of Natural Resources - Forest Management Division