

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron (County)	Located in:	Corner Code #
1. Public Land Survey	T 44N R 31W	M6
	T 44N R 31W	M3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

M3 Jul 01 1997
M6 Jun 25 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
(M6) Quarter corner common to Section 13 T44N-R31W and Section 18 T44N-R30W. Corner reestablished by single proportionate measurement in 1969 by A.O. Enger, RLS: "corner re-established on line between section corners 39.945 chains to north and to south...Corner monument 1" I.D. x 36" iron pipe with 4" aluminum cap. Witnesses to corner: B.Spruce 8 M66E 25.5 links, W.Spruce 5 S19W 9.5 links".
(M3) Corner common to Sections 1-12 T44N-R31W and Sections 6-7 T44N-R30W. Corner monumented in 1968 by A.O. Enger, RLS: "Corner replaced from stumps of two white pines believed to be original BT's...Corner monument: 1" iron pipe with 4" aluminum cap. Witnesses to corner: White Pine 12 S19E 23.5 links, White Pine 12 S39W 71.5 links".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M6) Found Enger's monument in good condition, as described, a 1" I.D. iron pipe capped with a 4" cast aluminum MDNR tablet, at record bearing and distance from the remains of the 1969 bearing trees. Both were recovered as rotting stumps. My measurements from the monument to adjacent section corners are 2633.42' N. and 2639.5' S. The monument was found 1.7' west of a straight line between these corners. I accepted the monument as a careful and faithful reestablishment of the position of the original corner. Left the monument in place and marked 4 new witnesses as described below. Corner recovered and witnessed by D.Lampela and B.Wheeler, Baraga District Office, MDNR.
(M3) Recovered the 1968 monument, as described, in good condition, and at record bearing and distance from the 1968 witnesses, both in good condition. Left the monument in place and marked three new accessories as described below. Corner witnessed by D.Lampela and B.Wheeler, Baraga District Office, MDNR.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M6) Found 1" pipe with 4" MDNR cap. Blazed and scribed the following:
18" W. Pine N86E 78.9' "1/4S NBT"
4" Spruce N74E 35.2' "1/4S NBT"
20" W. Pine N20W 71.5' "1/4S NBT"
5" Spruce S44W 21.7' "1/4S NBT"
Bearings are magnetic

(M3) Found 1" pipe with 4" MDNR cap. Blazed and scribed the following:
4" Maple N36W 24.4' "S1 NBT"
8" Maple N81E 16.0' "S6 NBT"
8" Squared cherry S63E 1.2' to notch
The 1968 wits: 24" W. Pine S13E 15.5',
16" W. Pine S43W 47.2'. Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date Sept. 8, 1997
Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division