

65.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron <u> </u> <small>(County)</small>	Located in:	Corner Code #
1. Public Land Survey	T <u>44</u> N R <u>31</u> W	<u> </u> M9 <u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Jun 25 1997

I, Stephan J. Szyszkoski, in a field survey on , 19 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
(M9) Corner common to Sections 24-25 T44N-R31W and Sections 19-30 T44N-R30W. Corner reestablished in 1969 by A.O. Enger, RLS, by proportionate measurement between original corners 1 mile South and 3 miles north. Corner monument: 1" I.D. x 36" iron pipe with 4" aluminum cap. Witnesses to corner: Yellow Birch 16 N87W 37 links, Sugar Maple 12 N1E 35 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M9) Recovered the 1969 monument as described, a 1" I.D. iron pipe capped with a 4" dia. cast aluminum MDNR tablet, in good condition, and at substantial record bearing and distance from the 1969 witnesses. The Y. Birch has been cut above the BH blaze. Scribing is easily visible on the stump. The Sugar was found in good condition but at N06E bearing. My measurements to monumented corners 3 miles north and 1 mile south are 239.57 ch and 79.80 ch. respectively. I did not measure to the corner 319.56 ch. north, noted on the Enger record as being three miles. I accepted the monument as a careful and faithful reestablishment of the position of the original corner. Left the monument in place and marked 3 new witnesses as described below. Corner witnessed by D.Lampela and B.Wheeler, Baraga District Office, MDNR.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M9) Found 1" pipe with 4" MDNR cap.

Blazed and scribed the following:

4" Ironwood N56W 29.2' "S24 NBT"


8" Basswood S80W 34.6' "S25 NBT"

7" Sugar S39E 45.9' "S30 NBT"

The 1969 wit: Sugar Maple N06E 35 links

Placed a squared sugar post adjacent.

Bearings are magnetic.



Signed by Stephan J. Szyszkoski

Date Sept. 8, 1997

Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division