

67.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron	Located in:	Corner Code #
(County)		
1. Public Land Survey	T <u>44N</u> R <u>31W</u>	<u>N5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Jul 01 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
(M5) Corner common to Sections 12-13 T44N-R31W, and Sections 7-18 T44N-R30W. Corner reestablished in 1969 by A.O. Enger, RLS, by proportionate measurement between corners 79.89 ch. North and 239.67 ch. South. The corner falls in a pond and was monumented by a witness corner placed on the section line S 0 deg 22 min W, 3.50 chains from the section corner. At the position for the witness corner, Enger placed a 1" I.D. x 36" iron pipe with 4" aluminum cap and marked the following: W. Pine 23 N09E 28.5 links, W. Pine 17 N50W 39 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M5) Recovered the 1969 monument as described, a 1" iron pipe capped with a cast aluminum tablet, squared, stamped "Wit. Cor. for 12-13-7-18 Cor. is N0 deg. 22'E 3.50 chains". The monument is in good condition and at record bearing and distance from the 1969 witnesses recovered as follows: W. Pine 30" N13E 19.0' found in good condition with blazes overgrown, W. Pine stump 17" N50W 25.8', only the notch visible. I determined via GPS observations that the extension of the section line from the south is actually N0 deg. 27' 20" W (true bearing), rather than Engers' bearing. I used my bearing, and the record 3.50 chains in computing the location of the section corner for use in a partial subdivision of Section 13 during the course of this survey. From the Section corner in the pond, I computed the distances to the corners noted in Part A above to be 79.85 ch. north and 239.52 ch. south. I accepted Enger's corner as a careful and faithful reestablishment of the position of the corner. Left the Witness Corner in place and marked 3 new accessories as described below. Corner re-witnessed by B. Wheeler and D. Lamplala, Baraga District Office, MDNR.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M5) Found 1" pipe with 1 x 2" square aluminum tablet for a witness corner.
Blazed and scribed the following:
14" W. Birch S09E 24.1' "WC BT"
12" W. Spruce S15W 58.0' "WC BT"
30" W. Pine N26W 44.0' "WC BT"
The 1969 wit: 30" W. Pine N13E 19.0'
Bearings are magnetic.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date Sept. 8, 1997

For the Michigan Department of Natural Resources - Forest Management Division