

68

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 44N R 31W	11
	T 44N R 31W	J1
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

J1 Jul 08 1997
J1 Jul 01 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(I1) Corner common to Sections 2-3 T44N-R31W and 34-35 T45N-R31W. Corner reestablished in 1968 by A.O. Enger, RLS. Corner was placed the original record distance of 40.00 ch. west of the 1/4 corner between Sections 2 and 35, rather than proportionate to the original record, for reasons stated on his certificate dated March 19, 1969. Corner monument: 1" I.D. x 36" iron pipe with 4" aluminum cap. Witnesses to corner: White Spruce 5 S27W 65.5 links, White Spruce 5 N88 1/2W 60.5 links, Trembling Aspen 6 N43E 27.5 links.
(J1) Quarter corner common to Section 2 T44N-R31W and Section 35 T45N-R31W. Corner reestablished in 1968 by A.O. Enger, RLS in a 22" W. Pine stump corresponding to description of the original corner monument. Set 1" I.D. x 36" iron pipe with 4" aluminum cap. Witnesses to corner: Forked Bl. Spruce 7 S12W 23 links, Bl. Spruce 6 N84W 106 links. Found no subsequent record.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I1) Recovered the 1968 monument, as described, in good condition, and at record bearing and distance from the stump remains of the two W. Spruce NBT's, neither one showing signs of the markings. No evidence exists of the Aspen NBT. Left the monument in place and marked 4 new accessories as described below. This corner is being recorded to update the accessories. Corner witnessed by D. Lampela and B. Wheeler, Baraga District Office, MDNR.
(J1) Recovered the 1968 monument, as described, with a 4" dia. cast aluminum Michigan Dept. of Natural Resources tablet, in good condition, and at record bearing and distance from Enger's witnesses, now both rotting stumps with measuring notch and scribing visible. Left the monument in place and marked four new witnesses as described below. Corner recovered and witnessed by D. Lampela and B. Wheeler, Baraga District Office, MDNR.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I1) Found 1" pipe with 4" MDNR cap.
Blazed and scribed the following:
5" W. Spruce N86E 31.7' "S35 NBT"
8" W. Spruce S17E 86.7' "S2 NBT"
5" R. Pine S49W 46.3' "S3 NBT"
2" W. Spruce N16W 26.4' "S34 NBT"
Bearings are magnetic.

(J1) Found 1" pipe with 4" MDNR cap.
Blazed and scribed the following:
16" Spruce S02E 30.8' "1/4S NBT"
16" Spruce S65W 71.5' "1/4S NBT"
3" Red Pine N07W 45.1' "1/4S NBT"
4" Spruce N79E 29.3' "1/4S NBT"
Squared a cut-off cherry 1.4' west of the corner. Bearings are magnetic.



Signed by

Stephan J. Szyszkoski

Date

Sept 8, 1997

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division