

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 44N R 31W	K10
	T R	
	T R	
	T R	
2. Property Controlling in Section	S 24 T 44N R 31W	14
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

14 Jul 08 1997  
K10 Aug 27 1997

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:  
(K10) Quarter corner common to Sections 25-26. Original corner now falls in the Michigamme Reservoir. Corner is shown on a map prepared for Wisconsin-Michigan Power Company titled "Michigamme River-Way Storage Dam Land Ties and Benchmarks" by Holland, Ackerman and Holland, Rev. 12/7/53, map G-154-66. Corner is described as "found 3" sq. post, set Concrete monument with brass cap 339 ft. North. Witnesses are: 4" Pop. S60E 1.5', 3" Pop. S80W 7.3', 3" Birch N45W 10.5". The WMPCO monument was recovered and described on a survey by John R. Garsko, PS 28410, in 1988 (project No. S-88130 for Coleman Engineering Co.) as "Fnd. 7" sq. tapered conc. monument w/3" sq brass cap".


(14-Sec. 24) South 1/16 corner between Section 24, T44N-R31W and Section 19 T44N-R30W. Corner established in 1969 by A.O. Enger, RLS on line between Section corner 19.972 ch. South and 1/4 Corner 19.972 ch. North. Corner monument: 1" I.D. x 36" iron pipe with 4" aluminum cap. Witnesses to corner: Basswood 13 N60E 50 links, Sugar Maple 13 S72W 33.5 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K10) Found a WMPCO concrete monument, a 7" truncated right rectangular concrete pyramid with a 3" square brass tablet affixed on top which is stamped "Wisconsin Michigan Power Company 44-31 1/4 25-26 339' S. to cor". The WMPCO witnesses were not recovered. Accepted the monument as a reference to the original corner and reestablished the corner due south (astronomic or true south) 339.00' from the monument. The computed corner position was not used to establish or reestablish any other corners during the course of this survey. Left the reference monument in place and marked four new witnesses as described below. Corner re-witnessed by B. Wheeler and D. Lampela, Baraga District Office, MDNR. From the monument, the water's edge is south 71 ft. The north edge of a cattail marsh is south 50 feet. (14-Sec. 24) Recovered the 1969 monument, as described, with a 4" dia. cast aluminum Michigan Dept. of Natural Resources tablet, in good condition, and at record bearing and distance from the 1969 witnesses, both found in good condition with overgrown blazes. Left the monument in place and marked two new accessories as described below. Corner re-witnessed by D. Lampela and B. Wheeler, Baraga District Office, MDNR.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K10) Found WMPCO concrete reference monument 339' N. of corner. Blazed and scribed the following bearing trees:	(14) Found 1" pipe with 4" MDNR cap. Blazed and scribed the following:
6" N. Pine S46E 18.0' "RM BT"	6" Sugar S14E 9.6' "1/16S BT"
9" Spruce N79E 25.1' "RM BT"	5" Sugar N48W 30.6' "1/16S BT"
9" Sugar N29W 37.6' "RM BT"	The 1969 witnesses:
8" Spruce S69W 15.2' "RM BT"	22' Basswood N63E 32.9'
Placed a squared spruce post adjacent.	18" Sugar S75W 22.1'
Bearings are magnetic.	Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date Sept. 8, 1997  
Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division