

71.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 44N R 31W	L3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Aug 26 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
(L3) Quarter corner common to Sections 1-12. Corner established in 1849 by John Burt: "West corrected, ...37.45 Cedar 18...40.11 Set Sugar gr. Section post, N. Pine 18 N03E 26, do 24 S40W 28...42.62 N. Pine 14...44.00 Top of ridge 20' N&S". Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L3) Original post and accessories not recovered. Found no acceptable evidence of the position of the original corner on the ground. Searched the corner area for more than six man-hours in an attempt to recover the bearing trees and the original line trees at 37.45 and 42.62 chains along this line. No evidence was found of the line trees. There are several N. Pine stumps and stump bottoms in the vicinity of the corner but no markings were found on any and no two will match the record. Reestablished the corner midway and on a line of mean true bearing between Section corners to the East and West. At the position for the corner, I placed a 1" I.D. x 3/2" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. The top of ridge noted above was found 3.3 chains west of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(L3) Set 1" pipe with 4" MDNR cap.
Blazed the following at 8H and root crown. These trees were not scribed.
24" W. Pine N27W 22.2'
15" W. Pine S88E 43.2'
12" W. Pine S26W 82.9'
5" Spruce S67W 22.4'
Made a notch in a 22" W. Pine stump 2 ft. above grnd S48W 2.8". Placed a 4" balsam post adjacent. Bearings are magnetic.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date Sept. 8, 1997

For the Michigan Department of Natural Resources - Forest Management Division