

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron	Located in:	Corner Code #
(County)		
1. Public Land Survey	T 44N R 31M	19
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Jul 08 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
(19) Corner common to Sections 22-23-26-27. Corner established in 1849 by John Burt: "Set corner of Secs. 22,23,26,27 W. Pine 14 N42W 37, W. Pine 12 S30E 37. West established between 22 & 27, 1.50 Enter open swamp SSE, 5.50 Stream 25L C N. sluggish, 7.00 Leave swamp C NW". Corner is shown on a map prepared for Wisconsin-Michigan Power Company titled "Michigan River-Way Storage Dam Land Ties and Benchmarks" by Holland, Ackerman and Holland, Rev. 12/7/53, map G-154-66. Corner is described as "set concrete monument with brass cap". Witnesses are 4" poplar S11E 15.1', 4" poplar S64W 60.1', 2" birch N35W 36.1".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
(19) Original post and accessories not recovered. There are several old, burnt W. Pine stumps on this hillside but no two were found to match the record. Recovered the WMPCO monument, a 7" truncated right rectangular concrete pyramid with a 3" square brass tablet affixed on top which is stamped "Wisconsin Michigan Power Company 44-31 22-23-26-27". The WMPCO witnesses were not recovered. The calls to the west (noted above) checked with the exception of the swamp edge 1.50 chains. It was found at about 0.5 chains west of the monument. Distance east to WMPCO mon and the 1/4 23/26 was found to be 2638.01'. Distance south to section corner was found 5246.5' (5280 R). Distance north to WMPCO mon. at 1/4 corner was meas. as 2646.72'. Distance north to reestablished SW corner of Section 2 was measured as 15837.8' (15840' R). Accepted the monument as the best available evidence of the position of the original corner. Left the monument in place and marked new bearing trees as described below. Corner placed and witnessed by B.Wheeler and D.Lampela, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(19) Found WMPCO concrete monument.
Blazed and scribed the following:
8" Red Pine S20E 30.2' "S26 NBT"
20" W. Pine S04E 66.0'(slope) "S26 NBT"
7" twin Maple N13W 15.0' "S22 NBT"
4" W. Pine N50E 18.9' "S23 NBT"
a 6' tall 4"x4" post was found adjacent.
Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 11-18-97
Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division