

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron  
\_\_\_\_\_  
(County)

Located In:

Corner Code #

1. Public Land Survey	T 44N R 31W	J3
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Sep 22 1997

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5				4			3				1
3										2			
4	7		8			9			10		11		12
5													
6	18		17			16			15		14		13
7													
8	19		20			21			22		23		24
9													
10	30		29			28			27		26		25
11													
12	31		32			33			34		35		36
13													

A. Description of original monument and accessories and/or subsequent restoration:  
(J3) Quarter corner common to Sections 2-11. Corner established in 1849 by John Burt. "Set Y. Birch qr. Sec. Post. Tam 14 S19E 24, Tam 14 N22W 10". From the original record: West true line between 2 and 11 "...1) 19.00 Enter swamp, 2) 21.80 Brook 10 L C SW, ...40.01 Set qr. Sec. post...3) 40.50 Leave swamp C SW, 4) 45.00 Top of Ridge 20 feet C SW, ...5) 68.50 Leave swamp N&S, 6) 80.03 Section corner".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J3) Original post and accessories not recovered. Found no record of subsequent monumentation. Reestablished the corner according to the original record as referenced above: items 1)-5) check very well. The courses of these calls are all acute to the section line and would not fit along a line either to the north or south. The corner position as determined from these calls is quite definitive. Distances east and west to adjacent corners measures 2635.6' and 2636.3', respectively. This retraced line was extended westerly and 13 was reestablished on it's terminus. The terminus of the line is in proper proportion to recovered corners 1 mile north and 2.5 miles south of 13. At the position for J3, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. From the corner monumented, I found a thin walled iron pipe, projecting approx. 4 ft. above ground S57W 35.9'. This pipe apparently represents an approximate position as it does not fit the original record. Corner placed and witnessed by B.Wheeler and D.Lampela, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J3) Set 1" iron pipe with 4" MDNR cap.

Blazed and scribed the following:

8" Spruce N12E 22.0' "1/4S NBT"

6" Spruce S37W 20.5' "1/4S NBT"

7" Spruce S82W 9.6' "1/4S NBT"

8" Twin Spruce N47W 25.2' "1/4S NBT"

Placed a squared spruce post adjacent.

Bearings are magnetic.



Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 11-18-97

For the Michigan Department of Natural Resources - Forest Management Division