

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Iron

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>44</u> N. <u>31</u> W. <u>31</u> 30	K13
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 19, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Section Corner 1, 2, 35, & 36, T43-44N, R31W

Cedar post	(Not found. Found 3"x3"x4' sq. black ash post.)
Cedar 10 N32E 16	(Found. NBT: Cedar 12 N82°W 27.3 ft. "NBT")
Cedar 9 N61W 11	(Probably found. NBT: Y. Birch 10 S31°W 11.2 ft. "NBT")
Cedar 12 S58E 26	(" ")
Cedar 10 S41W 26	(" ")

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Replaced wood post with monument described below. Post had been set by M. Davis, R.L.S. 16926, at record bearing and distance from a Cedar 10 N32E 16, now a weathered stump with lower notched blaze and scribe marks "BT" plain. Found rotted stumps (no marks) of other 3 BT's in proper places. Someone has set a 1" I.D. iron pipe S41°E 27.3 ft. from true corner, apparently in ignorance of the true corner location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.

Cedar 13 N53°E (mag.) 32.4 ft. "S36, NBT"
Cedar 12 N21°W (mag.) 40.2 ft. "S35, NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE December 21, 1976

CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
 Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

